



- Note:
1. Each screen interval lists the footage of the pipe perforations, not the top and bottom of screen joints.
  2. The interval of slough probably consist of sands and gravel of the Puye Formation.
  3. Westbay multiport sampling system (MP-55) casing not shown.
  4. Pipe-based screen: 4.5-in. I.D., 5.563-in. O.D., 304 stainless steel with s.s. wire wrap; 0.010-in. slot.
  5. Well sump interval: 980.6 to 1002 ft.